

ESRF Status and Upgrade

P. Elleaume



	2008	2009	2010*
Availability (%)	98.30	99.04	98.83
Mean time between failures (hrs)	64.50	75.80	70.80
Mean duration of a failure (hrs)	1.10	0.73	0.83

*updated on 18 October 2010







ESRF Publications 2005-2009

In 2009

- 1791 Referred Publications
- 200 high-impact publications

Cell, Nature, Nature cell biology, Nature materials, Science, PRL, PNAS, Angewante Chemie, Nano letters, EMBO J., APL, Advanced materials, JACS







- Improved resolution of the closed orbit measurement (Libera bpm electronics)
- Improved algorithm to correct magnets alignment errors

 \Rightarrow Vertical Emittance reduced and stabilised around 5pm (10 pm) in 7/8 and 2 x 1/3 (Uniform) filling modes

- More Skew correctors => < 2 pm in 2011
- See Presentation by A. Franchi

• New Orbit correction with 96 H &V correctors and 224 BPM operating from 0-1kHz under development, See **Presentation by K. Scheidt**



European Synchrotron Radiation Facility





Record Brilliance in ID27

European Synchrotron Radiation Facility





Upgrade Program 2009-2015

-Rebuild 10 beamlines

-Extend the Experimental Hall

-Renovation of Accelerator Systems

UP: Status of the EX2 project

European Synchrotron Radiation Facility

Experimental Hall Extension (EX2)





2010 - 2012

- APS validated May 2010
- APD validated 10 November 2010
- Works will start in September 2011
- **1**st long shutdown: 12-2011 to 03-2012
- 2nd shutdown: 08-2012

April 2013:

- Commissioning of buildings
- Long beamlines construction starts



UP: Status of the EX2 project

European Synchrotron Radiation Facility



Reduction of the Programme to accommodate budget cuts





ASD Technical Developments

•Renovation of Orbit monitoring

- 224 Libera in operation (2009)
- New Orbit stabilization system (2011)

Reduce the vertical emittance

- Add 32 skew quadrupole correctors (2011)

•Upgrade to 6m and 7 m ID Straights:

- ID30 and ID18 completed
- ID24 and ID20 scheduled for December 2010 and July 2011
- Production of High Gradient quadrupoles
- Insertion Devices:
 - 11 ID magnetic assemblies delivered
 - 4 revolver under manufacture
 - New cryogenic in-vacuum undulator under test, installation spring 2011
 - New 2.5 m long in-vacuum undulator under manufacture
- Beamlines Canting (x 4):
 - Permanent Magnet steerers delivered and shimmed
 - New sextupoles Ordered
- Solid State Power Amplifiers:
 - 1 MW of SSA Ordered in 2009
 - First 75 kW tower to be delivered January 2011
- HOM damped Copper RF cavities:
 - Two prototypes by end of 2010, the third one in spring 2011
- 300mA Operation:
 - Fully tested in Accelerator dedicated time
 - Few USM shifts scheduled in 2010

The European Light Source

XVIII ESLS Workshop, 25-26 November 2010

Slide: 11

O ESRF

2nd Cryogenic Perm. Und.

European Synchrotron Radiation Facility



2.5 m IVUs











- compact design (thickness <100 mm)
- optimized transverse flat field profile



Slide: 15

Bx II



ESRF

Permanent magnet dipole

European Synchrotron Radiation Facility



ESRF

High Gradient Quadrupoles



- 12 units manufactured by Antec
- Needed for 7 m straights

.

- Gradient 26 T/m
- Diameter 66 mm
- Prototype Delivered
- Magnetic Field Measurement of prototype at ALBA/ ESRF



Magnetic Measurement Bench

European Synchrotron Radiation Facility

Stretched Wire

- Magnetic center
- Harmonic analysis

Transfer to survey monument

- Reference tool
- Laser micrometer

Applications

- Quadrupoles
- Sextupoles
- Undulators
- Steerers





New quadrupole measurement bench

- Noise level similar to that of solid rotating coils
- Highly flexible and can be customized for high precision measurement of any type of magnet

Main results for Quadrupole measurement Magnetic center measurement

- Repeatability $< 1 \ \mu m$ for position measurements
- Repeatability < 10 μm for transfer to survey monuments

Double field integral measurement

Standard deviation $< 70 \mu$ rad on quadrupole direction

Harmonic measurements

- Normalized standard deviation $< 50 \ 10^{-6}$ on field integral (with respect to quadrupole field) on 30 mm radius
- Repeatability < 10 μrad on tilt measurements

Probably a revolution in Magnetic field measurement intrumentation for accelerator magnets

- Makes bucking coils obsolete (move wire along the primary field lines)
- Build Field Model in arbitrary profile (not limited to circle)
- Obtain Gradient of qaudrupole or sextupole vs hor. Posiiton with a much higher precision than rotating coils.
- The principle is to move the wire on a close path very close to the surface of yoke or magnet and reconstruct the surface current over that path
 - Improve the interpretation of field errors in term of geometrical errors

J. Chavanne, G LeBec, to be published





Single cell NC HOM damped cavity prototypes

0.5 to 0.8 MV
Design for 300...500 mA
Instability thresholds above 1A

3 power prototypes

RI, SDMS, Cinel

Tests with beam on Storage Ring: cavity by cavity in cell 25, after removal of SR cavity 5, from mid 2011



RI: Ferrite HOM absorber for IR thermal test at ESRF, April 2010



CINEL: 3 body sectors after machining of the water cooling channels, September 2010



This work, carried out within the framework of the ESRFUP project, has received research funding from the EU Seventh Framework Programme, FP7



RI: Body after e-beam welding of the HOM coupling sections, April 2010



SDMS: Body after e-beam assembly of the 3 sectors, November 2010

The European Light Source

XVIII ESLS Workshop, 25-26 November 2010



2. Contract for 7 SSA of phase 1 with ELTA









3. R&D – SSA using a Cavity Combiner



For ESRF application:

• 6 raws x 22 Columns x [600 ...800 W per transistor module]

\Rightarrow 75 ... 100 kW

 More compact than SOLEIL type coaxial combiners

Coupling: $\beta_{waveguide} \approx n_{module} \times \beta_{module} >> 1$

- Easy to tune if n_{module} is varied
- Reduction of losses \Rightarrow higher η

SSA with Cavity Combiner

- Mechanical design ready to build a 10 kW prototype (18 modules)
- Main goal: develop an adequate electrical & mechanical interface between RF modules & cavity, for easy plug in
- In parallel:
 - In house development of amplifier modules,
 - Using latest LDMOS-FETs
 - ➤ Goal:
 - Acquire expertise in SSA design,
 - Implement the design improvements
 - Prepare the future operation follow up
 - Set reference for coming procurements
- Prepare next step:
 - > Full scale prototype at 75...100 kW



4. New coupler using LHC window - CERN-ESRF-SOLEIL collaboration



Following financial difficulties of some ESRF partners a 6% Reduction of 2011 budget will be discussed at the next Council meeting (29th-30th November 2010) !

- Reduction of Investment as well as Personal costs
- Scale Down the Building Program
- Close some beamlines
- Concerning Accelerator Division
 - Stop investment for 300 mA operation
 - Reduce the RF program (Cavity)
 - Delay the 7 m beamlines upgrade